Sl. No.	Description of Items
1	Earthwork excavation by manual means in Ordinary soil involving an averag horizontal throw upto 2 meters and an average lift upto 0.5 m excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specification and direction of engineer in charge of the work
2	Providing and laying in positon plain cement concrete of mix M 7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted in foundation and plinth, including cost of all mateial, labour HOM of machinery curing complete as epr specification and direction of engineer in charge of the
3	Providing and constructing granite/trap/basalt size stone masonry in foundation in cement mortar 1:6 stone hammered dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of mateial labour curing complete as per specification and direction of enginner in charge of the work
4	Providing and constructing granite/trap/basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of mateials, labour, curing complete as per specification and direction of enginner in charge of the work
5	Providing and laying in position plain cement concrete of mix M 1:2:4 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour HOM of machinery, curing complete as per specification and direction of engineer in charge of the work
6	Providing TMT steel reinforcement for R.C.C work including straightening cutting, bending, hooking placing in position, lapping and/or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour HOM of machinry complete as per specification and direction of enginner in charge of the work.
7	Providing and removing centering shuttering, strutting propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, labour complete as per specification and direction of engineer in charge of the work
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the enginner in charge of the work lead 4 Km a) Basic rate for halage of mateirals as pe item average earrth of work 1.28 Tonne/Km for Rs. 2.00 /Km c) Add loading and unloading complete as per specificaion and direction engineer in charge of the work

CERTIFICATE

1 This is to certify that the contractor has completed the work satisfactorily.
2 The contractor has cleared the debries from the work sport
3 The contractor has used his own vehicles for the coveying the debries.
4 There are no departmental issues for the above work.